I. Constructing outhouses for No. 1 and 2 Blocks of Operators' Quarters.

No.	Items of work	Per	Quantity
1	Earthwork excavation, gravelly soil	C. yd.	35
2	Concrete foundation	C. ft.	312
3	Stone in mortar, foundation and basement	,,	867
4	Brick in mortar, superstructure	,,	1,389
5	Bond stones (3' x 1½' x ½')	Each	32
6	Stone slabs 4" to 6" thick, roughly dressed	S. ft.	91
7	Plastering with mortar	Sqr.	21·45
8	Pointing with mortar	,,	1·61
9	White and colour washing	,,	23·06
10	Mangalore tiles flooring on 3" concrete and cement pointing	,,	2·06
11	Roofing with Mangalore tiles on T. R. 2" x 1"	,,	7·60
12	Ridge tiles set in mortar	R. ft.	38
13	Ventilating tiles	Each	6
14	Honne eave board ordinary	R. ft.	116
15	Honneywood work with wood oiling	C ft.	25·41
16	Honney battened doors, 1¼" shutters	S. ft.	98
17	Honney windows with iron bars	,,	36
18	Honney glazed ventilators	,,	12
19	Painting with two coats of chocolate paint	Sqr.	367
20	Cleaning site and forming drain	Lumpsum	
21	Providing mortar and pestle	,,	,,
22	Building bath cisterns	Each	2
23	Cement pointing to roof	Sqr.	6·60

II. Converting the existing outhouses into six cooly quarters with additions.

1	Dismantling the existing roof complete	Sqr.	12·96
2	Removing the door frames and leaving the door ways as openings	Each	6
2a	Removing windows and inserting doors including necessary dismantling and repairs wherever necessary.	,,	6
3	Earthwork excavation	C. yd.	24
4	Stone in mortar foundation and basement	C. ft.	922
5	Burnt brick in mortar superstructure	,,	1,833
6	Stone slabs 4" to 6" thick, roughly dressed	S. ft.	190
7	Chunam pointing	Sqr.	1·63
8	Chunam plastering	,,	20·68
9	White and colour washing	,,	94·45
10	Concrete flooring, 3" thick	,,	7·15
11	Fixing old wood work with reepers using new nails	,,	12·96
12	Roofing with old Mangalore tiles with cement pointing	,,	12·96
13	Fixing old wall plates with tarring	R. ft.	144
14	Fixing old ridge tiles in mortar	,,	72
15	Roofing with new Mangalore tiles on T. R. 2" x 1" and cement pointing	Sqrs.	11·52
16	Honney wood work with wood oiling	C. ft.	55
17	Fixing old eave board using new nails	R. ft.	180
18	New honnewood eave board ordinary 9" to 1"	,,	32
19	Painting with one coat of chocolate paint	Sqr.	5·37
20	Unforeseen works such as replacing broken tiles, reepers, etc.	Lumpsum	1 item
21	Bond stones (3' x 1½' x ½')	Each	42
22	Repairs to existing Cuddapah slab flooring of rooms by raking up joints resetting slabs where necessary and cement pointing the whole afresh.	Sqr	6·00

S. G. FORBES,
Chief Electrical Engineer.

THE BANK OF MYSORE, LIMITED, BANGALORE.

Statement of the affairs of the Bank of Mysore, Limited, for the week ending 26th April 1923, published under Article 141 of the Articles of Association.

LIABILITIES	Rs.	ASSETS	Rs.
To Capital Receipts ..	20,00,000	By cash in hand and at Bankers.	30,17,821
,, Reserve Fund ...	9,75,000	,, loans and cash credit accounts.	1,10,61,169
,, Public and other deposits ..	1,52,90,465	,, bills discounted ...	3,67,772
,, Sundries ...	3,55,249	,, investments	33,87,128
		,, balance at Agencies ...	1,62,560
(Annas and pies omitted.)		,, dead stock	5,57,496
		,, Sundries	66,768
Total ..	1,86,20,714	Total ...	1,86,20,714

W. C. ROSE,
Manager.